

BLACK HAWK COUNTY IOWA:SS
Filed for record FEB 6, 2002 at
4:00 P.M. and recorded in Book _____
of _____ Page _____
Patricia A. Soss Recorder
Fee 1-5.00/
HELLAND ENGINEERING & SURVEYING


UNITED STATES PUBLIC LAND SURVEY CORNER CERTIFICATE
OF

SURVEY DONE ON THE NORTH & EAST LINES OF GOVERNMENT LOT 8 SEC. 19-T87N-R11W, NORTH LINE OF NE 1/4 SEC. 30.
NE CORNER: There are no Black Hawk County Engineer reference ties. WPA chaining notes for the North line of Sec. 29-T87N-R11W dated 8/18/1941 say they "will set S.C.M. later". WPA chaining notes for the North line of Sec. 30-T87N-R11W dated 8/18/1941 say they "carry on in winter" at Sta. 44+11.8 from the NW Corner of Sec. 30. Suspect the corner was never set. Dug 5'(N-S)x 40'(E-W)x5' deep trench centered at the distance-distance intersection from the W 1/4 Corner & N 1/4 Corner of Sec. 29. No evidence was found. Set 0.25'o.d. galvanized pipe at said distance-distance intersection in concrete w/No. 4 rebar in center (flush).
E 1/4 CORNER: Found concrete monument w/brass cap 0.4' deep per WPA notes dated 11/14/1939. Set No. 4 rebar on North side for magnetic detection.

PLAN VIEW



FILE NAME: 02-111C3.DRG



Surveyor under the laws of the State of Iowa.
Paul H. Holland 2/1/02
 Paul H. Holland
 License Number 6505
 My license renewal date is December 31, 2003.
 All pages or sheets are covered by this seal except:

<u>CORNER</u>	<u>SECTION</u>	<u>TOWNSHIP</u>	<u>RANGE</u>
NE CORNER	30	87N	11W
E 1/4 CORNER	30	87N	11W