



SLSI 9-94
BHC0 03-09

CORNER RESET FOR COLD-IN-PLACE RECYCLE & H.M.A. RESURF. PROJECT LFM-503--7X-07.
PRIOR TO RESURF. PROJECT, FOUND 3/8" PIN FROM CURRENT CORNER CERT. OF RECORD AND
TEMP. REF. CORNER LOC. PER TRK GPS. AFTER 4" DEEP MILL & RECYCLE COURSE, NO
SOUNDING REMAINED AND NO EXCAVATION DONE @ LOCATION. AFTER +3" H.M.A. RESURF.
COURSE, RESET CORNER WITH 5/8" (#5) x ±8" L REBAR LOCATED @ ±0.15' SOUTH OF H.M.A.
JOINT AND ALIGNED WITH FENCE LINE TO NORTH.

PREPARED BY: S.S. & G.T. 12/4/12

INDEX OF ABBREVIATIONS

(M) = "Measured" Dimension	"NP" = Reflectorless EDM Meas.
(P) = "Platted" Dimension	"MLM" = Indirect Measure
(R) = "Record" Dimension	"CM" = Concrete Monument
(C) = "Calculated" Dimension	"SM" = Survey Marker Spike/Tag
"GSS" = Iowa Geodetic Survey	"PK" = PK/MAG Nail Brand Style
"WPA" = Works Progress Admin. Survey	
"G" = per George Miller Survey (BHC Surveyor 1858-1860)	
"B" = per John Ball Survey (BHC Surveyor 1866-1891)	
"N" = per Nathan Barber Survey (BHC Surveyor 1908-1931)	