

File 2009-00019921

PH.# (319) 291-2419
FAX.# (319) 291-2461

SLSI 9-94
CERT 12-96

Land Survey Monuments situated in Section 35 , Township 87 N ,
Range 14W , of the Fifth Principal Meridian, BLACK HAWK County, Iowa.
Previously recorded in Misc. Book 332 , Page 933 , in County Recorder's Office.

(Show reason for preparing this certificate): The corner monument has been Replaced or Modified, per Ia. Code 355.11(1)(c)

(Evidence and detailed procedures used in establishing the corner position(s) and monumentation found or placed.)

Monument Description and Remarks: N. 1/4 COR. FND. #4 (1/2") RBR. PER CURRENT RECORD, LOC. IN PCC PVMT. UNDER ACC OVERLAY IN SURFACE PATCH. TEMP. REFERENCED CORNER w/CONSTRUCTION TIES PRIOR TO RUBBLIZED 6" Dp. PCC PVM'T., AND NEW 7" Dp. HMA/ACC RESURFACING @ 22' WIDE. CORNER @ ± CL. RD. AND ALIGNED (±) w/FENCE TO SOUTH. CORNER RESET WITH ±7"L. x 5/8" REBAR FLUSH WITH HMA PAVEMENT, AND LOCATED ±3" NORTH OF C.L. HMA PAVING JOINT.


PLAN VIEW
"NOT TO SCALE"

BHco Hist. Ties: BK. #1000 (35) 87-14

FIELD BOOK: BHco. #488 p.13

(Show a minimum of three reference ties to durable physical objects, relevant monuments and physical conditions that will enable recovery of the corner.)

1.) TIES PER EDM MEASURE IN NON-PRISM
MODE, WHILE UTILIZING "INDIRECT/MLM"
MEASURE.



S.P.C., Ia. N. Zone, USft

N.= 3578402.48


E.= 5206302.97

(NAD83-2007 "BHco07", RTK Obs.)

FIELD SURVEY: G.T. & J.Z 07/29/08

PREPARED BY: G.T. & J.Z. 4/13/09

LIST CORNERS TO BE INDEXED



I hereby certify that this land surveying document was prepared and the related survey work was performed by me or under my direct personal supervision and that I am a duly licensed Land Surveyor under the laws of the State of Iowa.

Geoffrey Allen Tinker 09/22/2009 (date)

License Number 15748

My license renewal date is December 31, 2010

Pages or sheets covered by this seal:

This Land Corner Certificate Only.

<u>Corner</u>	<u>Section</u> -	<u>Township</u> -	<u>Range</u>
N. 1/4	35	87 N	14 W
S. 1/4	26	87 N	14 W

INDEX OF ABBREVIATIONS

(M) = "Measured" Dimension "N" = Reflectorless EDM Meas.
(P) = "Platted" Dimension "MLM" = Indirect Measure
(R) = "Record" Dimension "CM" = Concrete Monument
(C) = "Calculated" Dimension "SM" = Survey Marker Spike/Tag

"GS" = Iowa Geodetic Survey
"WPA" = Works Progress Admin. Survey
"G" = per George Miller Survey (BHC Surveyor 1858-1860)
"B" = per John Ball Survey (BHC Surveyor 1866-1891)
"N" = per Nathan Barber Survey (BHC Surveyor 1906-1931)