



SLSI 9-94
CERT 03-09

Monument Description and Remarks: N.E. COR. FOUND 2 1/2" Ø I&DOT ALUM. CAP IN ACC
CORE HOLE, AND COTTON GIN SPIKE LOC. 1.00' NORTH OF ALUM. CAP, PER CURRENT RECORD.
CLEANED ACC CORE HOLE TO ±4" Dp. THRU ACC OVERLAY TO PCC PAVEMENT, w/NO
FURTHER MONUMENTATION FND. IN PCC. TEMP. REF. BOTH w/RTK GPS (TWO LINE w/WT.
AVG.), THEN MILLED 2" EXIST. ACC OVERLAY & ADDED 5" H.M.A./A.C.C. OVERLAY. TRUE
CORNER (CLOSING) HEREIN TIED FOR RECORD, WITH BOTH CORNER'S BEING RESET WITH #5
(5/8") x ±7" L. REBAR PER RTK GPS REF.'S AND RETIED. TRUE CORNER (T.C.) LOCATED @
±0.16' NORTH OF C.L. H.M.A./A.C.C. PAVING JOINT, WITH AMENDED CORNER (A.M.) LOCATED 1.01'
SOUTH OF TRUE CORNER & ±0.85' SOUTH OF C.L. PAVING JOINT. LOCATION OF TRUE CORNER
NOT VERIFIED TO GEOM. REFERENCE EAST (RECORD INFO. ONLY). PREV. NAIL BETWEEN
CORNER'S (P.I. STATED, YET "P.O.T." STA. 749+82.3 PER I&DOT 1955) "NOT FND.", NOR RESET.

PREPARED BY: G.T. & J.Z. & D.B. 9/22/09

(M) = "Measured" Dimension	"NP" = Reflectorless EDM Meas.
(P) = "Platted" Dimension	"MLM" = Indirect Measure
(R) = "Record" Dimension	"CM" = Concrete Monument
(C) = "Calculated" Dimension	"SM" = Survey Marker Spike/Tag
"IGS" = Iowa Geodetic Survey	
"WPA" = Works Progress Admin. Survey	
"W" = per George Miller Survey (BHoC Surveyor 1858-1860)	
"B" = per John Ball Survey (BHoC Surveyor 1866-1891)	
"N" = per Nathan Barber Survey (BHoC Surveyor 1906-1931)	



This Land Corner Certificate Only.