



SLSI 9-94
CERT 12-96

Monument Description and Remarks: N. 1/4 COR. FOUND #5 REBAR LOCATED $\pm 1.1'$ SOUTH OF SOUTH EDGE ACC IN SHOULDER & ALIGNED \pm WITH FENCE LINE SOUTH, PRIOR TO RESURF. PROJECT. TEMP. REF. w/RTK GPS (TWO LINE w/WT. AVG.), THEN MILLED 2" EXIST. ACC PAVEMENT & ADDED 5" H.M.A./A.C.C. OVERLAY. CORNER LOC. ONLY AFFECTED BY ACC/HMA ENTR. FILLET PAVED OVER EXISTING SHOULDER. CORNER **RESET** WITH #5 (5/8") \times $\pm 7"$ L. REBAR PER RTK GPS REF., AND RETIED. LAND CORNER IS LOC. IN ACC/HMA FILLET BEING $\pm 1.1'$ SOUTH OF SOUTH EDGE (EXTENDED THRU FILLET) OF ACC/HMA PAVING & ALIGNED $\pm 1.3'$ WEST OF FENCE LINE SOUTH. CORNER CALC.'S @ "0.28' SOUTH" OF CALC.'ED TRUE CORNER (CLOSING) ONTO SOUTH LINE OF S.W. 1/4 SECTION 36-T89-R11, AS OBSERVED.

FIELD SURVEY: G.T. & J.Z. & D.B. 06/23/09
PREPARED BY: G.T. & J.Z. & D.B. 9/22/09

This Land Corner Certificate Only.

(M) = "Measured" Dimension "NP" = Reflectorless EDM Meas.
(P) = "Platted" Dimension "MLM" = indirect Measure
(R) = "Record" Dimension "CM" = Concrete Monument
(C) = "Calculated" Dimension "SM" = Survey Marker Spike/Tag

IGS = Iowa Geodetic Survey
WPA = Works Progress Admin. Survey
"G" = per George Miller Survey (BHC Surveyor 1858-1860)
"S" = per John Ball Survey (BHC Surveyor 1866-1891)
"N" = per Nathan Barber Survey (BHC Surveyor 1908-1931)