



SLSI 9-94
CERT 03-09

Monument Description and Remarks: N.E. COR., FOUND 2½"Ø ALUM. CAP STABLE IN
ACC CORE HOLE (±5" Dp. ACC OVERLAYED PCC PAVEMENT), PER CURRENT RECORD. DOWN
±5" Dp. TO PCC PVM'T. & FOUND LEAD PLUG IN PCC SLAB. TEMP. REF. CORNER w/RTK
GPS (TWO LINE w/WT. AVG.), AND MILLED 2" EXIST. ACC OVERLAY & ADDED 5" H.M.A.
OVERLAY. 1955 PAVING PLANS REF. AS STA. 335+48.5 @ 0.4' LT. (N.) OF C.L. RD. GEOM.
w/P.O.T. @ 335+82.0, PER DETAIL IN COR. CERT. FOR S.E. COR. SECT. 31-T89-R11. CORNER
RESET w/#5 (5/8") x ±7" L. REBAR PER RTK GPS REF., BEING LOC. 0.52' NORTH OF C.L.
NEW PAVING JOINT & ALIGNED ± w/C.L. OF McSTAY RD. SOUTH. CORNER CALC.'S AT 0.44'
"SOUTH" OF TRUE CORNER (CLOSING) ONTO SOUTH LINE OF S.E. 1/4 SECTION 31-T89-R11,
AS OBSERVED. NO CURRENT CERT. OF RECORD.

(M) = "Measured" Dimension "NP" = Reflectorless EDM Meas.
(P) = "Platted" Dimension "MLM" = indirect Measure
(R) = "Record" Dimension "CM" = Concrete Monument
(C) = "Calculated" Dimension "SM" = Survey Marker Spike/Tag

"ICS" = Iowa Geodetic Survey
"WPA" = Works Progress Admin. Survey
"G" = per George Miller Survey (BHC Surveyor 1858-1860)
"B" = per John Ball Survey (BHC Surveyor 1866-1891)
"N" = per Nathan Barber Survey (BHC Surveyor 1908-1931)

