

PROOF FILED FOR RECORD JAN 20, 2003, AT 3:00 P.M. FEE N/C

COMPARED:

BLACK HAWK COUNTY RECORDER

BLACK HAWK COUNTY ENGINEER'S OFFICE

PREPARED BY: BLACK HAWK COUNTY ENGINEERS OFFICE
316 E. FIFTH STREET, ROOM 211 WATERLOO, IOWA 50703

PH.# (319) 833-3008
FAX.# (319) 833-3139

SLSI 9-94
CERT 12-96

UNITED STATES PUBLIC LAND SURVEY CORNER CERTIFICATE OF

Land Survey Monuments situated in Section 04 , Township 90 N ,
Range 11 W , of the Fifth Principal Meridian, BLACK HAWK County, Iowa.
Previously recorded in Misc. Book N/A , Page N/A , in County Recorder's Office.

(Show reason for preparing this certificate, the evidence and detailed procedures used in establishing the corner positions and monumentation found or placed.)

Monument Description and Remarks: N.E. CORNER SECTION 04-90-11
FOUND C.M. LAYING ON SIDE ALONG FIELD EDGE. RE-ESTABLISHED C.M.
USING FND. RECORD TIE, PER W.P.A. DTD. 12-11-1939. FND. TIE HELD AS
WITNESS POINT. UTILIZED FOUND "U" SHAPED IRON FROM RECORD SURVEY
BY PLS #1128, AND ESTABLISHED LINE FROM FND. NORTH 1/4 CORNER TO
"EAST" THROUGH IRON TO INTERSECT WITNESS TIE. C.M. RE-SET, PER NOTE.

PLAN - VIEW

(Show a minimum of three reference ties to durable physical objects, relevant monuments and physical conditions that will enable recovery of the corner.)

NOTE: ALL DISTANCES PLUMB

NOT TO SCALE

S.M. = DENOTES "SURVEY MARKER"

EST. "X" NAILS
S.W. FACE
22" HICKORY
@ 18" HT.

EST. "X" NAILS
S./S.W. FACE
TWIN 18" OAKS
@ 25" HT.

EST. S.M. TAG
W/ NAIL @
TOP S. CENTER
48" STUMP
@ 36" HT.

N. 1/4 COR.
4-90-11
FND. STD. C.M.
(TIES BY "OTHER")


E. 1/16 CORNER —
FND. "U" SHAPED
IRON w/ POST per
PLS #1128, 1933.
(Painted Orange, w/
painted steel posts
to North. "ACCEPTED"
w/ TIES BY "OTHER")

FND. "X" NAILS
5" DEEP INTO
E./N.E. FACE
TWIN 18" HICKORY
@ 34" HT. (HELD)

FIELD SURVEY: G.T. & C.W. 12/13/02
PREPARED BY: G.T. & C.W. 01/20/03

PREPARED BY: G.T. & C.W. 01/20/03

CERTIFICATION



I hereby certify that this land surveying document was prepared and the related survey work was performed by me or under my direct personal supervision and that I am a duly licensed Land Surveyor under the laws of the State of Iowa.

Geoffrey Allen Tinker 01/20/03
(date)

License Number 15748

My license renewal date is December 31, 2004

Pages or sheets covered by this seal:

This Land Corner Certificate Only.

LIST CORNERS TO BE INDEXED

<u>Corner</u>	<u>Section</u>	<u>Township</u>	<u>Range</u>
N.E. COR.	04	90 N	11 W
N.W. COR.	03	90 N	11 W