

Richard L. King

BLACK HAWK COUNTY ENGINEERS OFFICE

PREPARED BY: BLACK HAWK COUNTY ENGINEERS OFFICE
316 E. FIFTH STREET, ROOM 211 WATERLOO, IOWA 50703

PH.# (319) 833-3008
FAX.# (319) 833-3139

SLSI 9-94
CERT 12-98

UNITED STATES PUBLIC LAND SURVEY CORNER CERTIFICATE OF
Land Survey Monuments situated in Section 32, Township 90 N,
Range 12 W, of the Fifth Principal Meridian, BLACK HAWK County, Iowa.
Previously recorded in Misc. Book N/A, Page N/A, in County Recorder's Office.

(Show reason for preparing this certificate, the evidence and detailed procedures used in establishing the corner positions and monumentation found or placed.)

Monument Description and Remarks: FOUND #5 REBAR LOC. @ +/- ELV. 1002.3' (29) AT INTERSECTION OF DUNKERTON AND SCHENK ROADS PRIOR TO PROFILE RECONSTRUCTION IN 2003, TO ELV. +/- 997.8 WITH NO STD. WPA C.M. FOUND DURING CONSTRUCTION. TEMP. REF. PER RTK GPS (S.P.C.) AND RE-EST. 8"x#5 RBR. w/ 2" ALUM. CAP FLUSH w/ ACC SURF. @ +/- C.L. INT. HELD FILE, PENDING 2004 RE-SURF. PROJECT IMPACT, & FILED FOR RECORD.

PLAN - VIEW

(Show a minimum of three reference ties to durable physical objects, relevant monuments and physical conditions that will enable recovery of the corner.)


NOTE:

NOT TO SCALE

REF. TIES per EDM MEASURE

"S.M." DENOTES "SURVEY MARKER"

Sectionline Distances Denoted @
1/x (x=Sc.) w/o Ellipsoid Factor
considered.



BLUE SPRUCE
EST. "TYP." @
S. FACE 26"
CONIF. @ 18" HT.

EST. MAG NAIL
w/ S.M. TAG (TYP.)
E. FACE P.P.
@ 15" HT.

EST. "TYP." @
E.-S.E. FACE 14"
CONIF. @ 6" HT.

N. 1/4 COR.
32-90-12,
PER TIES

-DUNKERTON RD.-
(A.C.C.)

N. 1/4 COR.
33-90-12,
PER TIES

2638.16' (M)

179°49'37"

94.98'

113.57'

2647.90' (M)
vs. 2647.95' (R)

S. EDGE ACC

S.P.C. (NAD83) 1A. N. ZONE :

N: 3673296.203
E: 5250342.689
Sc.: 0.9999468016
Conv.: 0°-49'-41"
Classif.: Second, Cl. II

ACC FILLET JOINT

END ACC


(Gravel)

(R) = Denotes "Record" Distance per
Survey, MISC. Bk. 312 p. 936

FIELD SURVEY: G.T. & C.W. AUGUST, 2003
PREPARED BY: G. TINKER 08/23/04

CERTIFICATION

LIST CORNERS TO BE INDEXED



I hereby certify that this land surveying document was prepared and the related survey work was performed by me or under my direct personal supervision and that I am a duly licensed Land Surveyor under the laws of the State of Iowa.
Richard L. King
Richard L. King
License Number 3890
My license renewal date is December 31, 2005
Pages or sheets covered by this seal:
This Land Corner Certificate Only.

Corner	Section	Township	Range
N.E. COR.	32	90 N	12 W
S.E. COR.	29	90 N	12 W
N.W. COR.	33	90 N	12 W
S.W. COR.	28	90 N	12 W