



SLSI 9-94
BHCO 03-09

Monument Description and Remarks: N.E. COR. N.W.1/4-N.W.1/4;
PRIOR TO H.M.A. RESURFACING PROJ. (#STP-S-C007(106)--5E-07), FOUND 5/8" REBAR PER
CURRENT RECORD & TEMP. REF. PER RTK GPS. HISTORICAL COUNTY ENG. TIES (AS NOTED,
PREV. STA. 224+17.1) NOT REFERENCED IN CURRENT RECORD. EXISTING A.C.C. MILLED -2",
w/ SOUNDING (FAINT) REMAINED @ ± RTK REF. LOC. AND NO FURTHER EXCAVATION DONE.
RESURFACED WITH +4" H.M.A. (2" INT. & 2" SURF.). AFTER H.M.A. RESURFACING, RESET
5/8"x±7"L. (#5) REBAR LOCATED AT ±0.60' EAST OF CENTERLINE PAVING JOINT AND
ALIGNED WITH ± C.L. OF SIDEROAD TO WEST. DEFL. (CORNER) ANGLE DENOTED FOR 16th
LINE TO N. & S. PER COGO OF RTK GPS MEAS. CORNERS (AS OBSERVED).

(M)	= "Measured" Dimension	"NP" = Reflectorless EDM Meas.
(P)	= "Platted" Dimension	"MLM" = Indirect Measure
(R)	= "Record" Dimension	"CM" = Concrete Monument
(C)	= "Calculated" Dimension.	"SM" = Survey Marker/Tag
"GS"	= Iowa Geodetic Survey	"PK" = PK/MAG Nail Brand Style
"WPA"	= Works Progress Admin. Survey	
"Φ"	= per George Miller Survey (BHC Surveyor 1858-1860)	
"Δ"	= per John Ball Survey (BHC Surveyor 1866-1891)	
"N"	= per Nathan Barber Survey (BHC Surveyor 1908-1931)	